

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/20/06

CORNER DESIGNATION: 3N31, N-7, The North One-Quarter Corner of Section 20.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne in 1861, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. For 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1 S17
4 S20
2006
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure between the reestablished Southwest and Southeast corners of Section 17, holding existing North-South field line for departure at corner point. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" by 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

A silver Deep-1 magnet buried 22" below ground level bears North 47° East, 36.9 feet.
A blue Deep-1 magnet buried 22" below ground level bears South 35 1/2° East, 45.1 feet.
A purple Deep-1 magnet buried 22" below ground level bears South 38 1/2° West, 42.6 feet.
An orange Deep-1 magnet buried 22" below ground level bears North 48 1/2° West, 37.8 feet.
Buried bearing object signs with magnets. Set steel fence post with witness post sign 1 foot North of monument.

LOCATION AND COMMENTS: Corner is located in a North-South field line, between fields.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 757305.69
E = 8594287.90

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31N7

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

06-462-C