

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 04/13/06

CORNER DESIGNATION: 3N31, R-11, The South One-Quarter Corner of Section 21.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E  
1/4 S21  
4 S28  
2006  
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure between the reestablished Southwest and Southeast corners of Section 21. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 22" below ground level bears North 44 1/2° East, 31.1 feet.
  - A blue Deep-1 magnet buried 22" below ground level bears South 32° East, 34.8 feet.
  - A purple Deep-1 magnet buried 22" below ground level bears South 42° West, 34.9 feet.
  - An orange Deep-1 magnet buried 22" below ground level bears North 45° West, 30.3 feet.
- Buried bearing object signs with all magnets. Set steel fence post with witness sign attached 1 foot West of the monument.

LOCATION AND COMMENTS: Corner is located in poorly defined North-South field line, there is a indefinite field line extending East. There is a loose 12 x 12 x 18" volcanic porous stone near the corner point.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 752024.71  
E = 8599633.77

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31R11

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-08*