

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 04/19/06

CORNER DESIGNATION: 3N31, R-19, The South One-Quarter Corner of Section 23.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. post.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E  
1 S23  
4 S26  
2006  
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure between the Southwest and Southeast corners of section 23. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 22" below ground level bears North 30 1/2° East, 36.7 feet.
  - A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 87 1/2° East, 71.3 feet.
  - A purple Deep-1 magnet buried 22" below ground level bears South 45° West, 43.2 feet.
  - A 3/4" brass washer stamped "PLS 1106" 1 foot above ground level in UECA power pole No. 265900 bears North 84 1/2° West, 128.0 feet.
- Buried bearing object signs with magnets. Attached bearing object signs to power pole and iron rebar. Set steel fence post with witness sign 1 foot East of monument.

LOCATION AND COMMENTS: Corner is located in a poorly defined East-West field line with a power pole line running East-West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 752070.87  
E = 8610207.90


FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31R19



*renews 6-30-08*