

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/20/06

CORNER DESIGNATION: 3N31, R-21, The Southwest Corner of Section 24.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D. S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for to Secs. 23 & 24, 25 & 26.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
S23|S24
S26|S25
2006
PLS 1106

MONUMENT SET:

Accepted fence corner with ancient fence running South and field line West. A field line extending North is about 10 feet East of North. There are scattered remains of an old fence extending East. At accepted corner position, set a 2 3/8 " brass cap on 1 1/4" x 30" galvanized iron pipe with top 2" above ground level and surrounded with mound of stones and earth. Monument marked as shown in monument marking detail.

From which:

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 35 1/2° East, 66.4 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 47° East, 31.9 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 23 1/2° West, 38.2 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears South 89 1/2° West, 36.9 feet.

Attached bearing object signs to all rebar accessories. Set steel fence post with witness sign attached 2 foot North of monument.

LOCATION AND COMMENTS: Corner is located at an old fence corner with fence extending South and a field berm extending West. A field line extending North is 10'+- East of corner.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 752066.77
E = 8612854.58


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31R21



William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08