

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/21/06

CORNER DESIGNATION: 3N31, V1, The Southwest Corner of Section 30.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by David P. Thompson, under Contract No. 81, dated July 8, 1859. Record states: Set post for corner to Secs. 30, 31, 25 & 36 and build mound of earth with pits, trench & c., as per instructions. J.C. Arnold, in County Road Survey No. 265, calls this corner at the intersection of his County Road No. 265, (North-South) and the Pendleton-Echo Road, (East-West).

MONUMENT AND ACCESSORIES FOUND: None. Held intersection of center lines of Yoakum Road, (North and South), with Temple Road, extending West, at best remaining evidence of the original corner location.

MONUMENT MARKING DETAIL:

T3N
R30E R31E
S25|S30
S36|S31
2006
PLS 1106

MONUMENT SET:

At reestablished corner point, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 8" below road surface. Monument marked as shown in monument marking detail.

A 5/8" x 24" iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 70 1/2° East, 31.2 feet.

A 3/4" brass washer stamped "PLS 1106" 1.5 foot above ground in a UECA power pole no. 310900 bears South 39 1/2° East, 31.7 feet. Attached witness post sign to pole.

A 3/4" brass washer stamped "PLS 1106" 1 foot above ground in a UECA guy pole bears South 56 1/2° West, 39.5 feet.

A 3/4" brass washer stamped "PLS 1106" 1.5 foot above ground in a UECA power pole no. 259000 bears North 53 1/2° West, 44.2 feet.

Attached bearing object signs to rebar accessories and to UECA poles with brass washers.

LOCATION AND COMMENTS: Corner is located in the intersection of center lines of Yoakum Road North and South, and Temple Road West. Corner is slightly North of the North edge of a private land extending East.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 746609.50

E = 8586336.64

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31V1

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08

06-462-C