

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 04/13/06

CORNER DESIGNATION: 3N31, V-19, The South One-Quarter Corner of Section 26.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E  
1/4 S26  
S35  
2006  
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure between the reestablished Southwest and Southeast corners of Section 26. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 22" below ground level bears North 49° East, 29.8 feet.
  - A blue Deep-1 magnet buried 22" below ground level bears South 37 1/2° East, 33.1 feet.
  - A purple Deep-1 magnet buried 22" below ground level bears South 50 1/2° West, 36.9 feet.
  - An orange Deep-1 magnet buried 22" below ground level bears North 46° West, 32.2 feet.
- Buried bearing object signs with all magnets. Set steel fence post 1 foot West of monument and attached witness sign.

LOCATION AND COMMENTS: Corner is located in a East-West field berm between farmed fields.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 746765.56  
E = 8610280.71


FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Witnesses: Jason Wells, LSIT

/3N31V19

Surveyor's Seal



*William R. Wells*



*renews 6-30-08*