

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 07/09/13

CORNER DESIGNATION: 3N32, A17, The Northwest Corner of Section 2.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Thompson, under GLO Contract 106, dated August 1864, notes state: Set post for corner to Secs. 2, 3, 34, 35 in mound of Earth with charred stake, pits, trench, &c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R32E  
S34|S35  
S3 | S2  
T3N  
2013  
PLS 54657

MONUMENT SET: Held the intersection of the centerline of Midway Road with a field line extending North as best remaining evidence of the original corner position. There is an old locust post set in the field line just North of the road. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, 10" below road surface, stamped as stated in "Monument Marking Detail", from which:

A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54756" bears North 52° East, 37.7 feet.

A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54756" bears South 57 1/2° East, 37.9 feet.

A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54756" bears South 61 1/2° West, 42.5 feet.

A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54756" bears North 49° West, 34.9 feet.

Attached bearing object signs to all accessories.

LOCATION AND COMMENTS: At centerline of Midway Road with field line North.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 773687.20'  
E= 8639193.27'

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy

\3N32A17

