

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/31/13

CORNER DESIGNATION: 3N32, E21, The Southwest Corner of Section 1.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under GLO Contract dated September 1864, notes state: Set post for corner to secs 1, 2, 11 & 12 in mound of earth with charred stake pits & as per instructions

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
S2|S1
S11|S12
2013
PLS 54657

MONUMENT SET: Held the intersection of the centerline of Campbell Road with a old field berm extending East as the best available evidence of the original corner point, At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap 12 inches below road surface, stamped as stated in "Monument Marking Detail", from which:
A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54647" in road bank, bears North 19° East, 41.8 feet.
A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54647" in road bank, bears South 79° East, 22.9 feet.
A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54647" in road bank, bears South 22° West, 46.9 feet.
A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54647" in road bank, bears North 29° West, 45.7 feet.
Attached bearing object signs to all accessories.

LOCATION AND COMMENTS: Located at the centerline of Campbell Road with a field berm extending East.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:
N= 768429.36'
E= 8644544.99'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

\3N32E21

