

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 09/23/13

CORNER DESIGNATION: 3N32, G17, The West One-Quarter Corner of Section 11.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of Earth with charred stake pits & c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E  
1/4  
S10 | S11  
2013  
PLS 54657

MONUMENT SET: Held the projection of a field line coming from the South with the centerline of a road extending West as the best remaining evidence of the original corner location. At the reestablished corner position, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 6" below ground level in grain bin area, top marked as shown in "Monument Marking Detail", from which:

A 5/8" iron rod with a 1 1/4" purple plastic cap, stamped "Wells Surveying, PLS 54657", bears North 55° East, 61.5 feet, (no tag).

A 5/8" iron rod with a 1 1/4" purple plastic cap, stamped "Wells Surveying, PLS 54657", nailed to wood board behind rebar, bears South 30° East, 35.7 feet.

A blue deep-1 magnet, buried 20" in the ground, bears South 42° West, 42.3 feet.

An orange deep-1 magnet, buried 20" in the ground, bears North 54 1/2° West, 42.2 feet.

Buried bearing object tags with magnets.

LOCATION AND COMMENTS: Corner at projection of field line from the South and centerline of road extending West, in grain bin area.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 765675.09'  
E= 8639346.34'

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy

\3N32G17



RENEWS: 6-30-14