

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 08/22/13

CORNER DESIGNATION: 3N32, J05, The Northwest Corner of Section 17.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for corner to secs 7, 8 17, & 18 in mound of Earth with charred stake pits & c as per instructions. The corner shows on an undated map by F.B. Hayes but there are no notes regarding this corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
S7 | S8
S18 | S17
2013
PLS 54657

MONUMENT SET: Held a point 1 foot East of the end of a fence extending West as best remaining evidence of the original corner position and reestablished corner by setting a 2 3/8" brass cap on a 1 1/4" galvanized iron pipe with top flush with ground marked as shown in "Monument Marking Detail", from which:

- A silver deep-1 magnet, buried 20" in ground, bears North 44 1/2° East, 33.2 feet.
 - A pink deep-1 magnet, buried 20" in ground, bears South 52 1/2° East, 32.9 feet.
 - A blue deep-1 magnet buried 20" in ground, bears South 32 1/2° West, 26.6 feet.
 - An orange deep-1 magnet buried 20" in ground, bears North 44° West, 37.5 feet.
- Buried bearing object tags with magnets. Nailed witness post sign to railroad tie post by monument.

LOCATION AND COMMENTS: Corner located at a point 1 foot East of the end of a fence extending West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:
N= 762729.21'
E= 8623537.18'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy
3N32J05

