

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/21/04

CORNER DESIGNATION: N-13, The Southeast Corner of Section 16, Township 3 North, Range 32 East, W.M., Umatilla County, Oregon.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by David P. Thompson, under GLO Contract No. 106, dated August 16, 1864. Record states: Set post for corner to Secs. 15, 16, 21 & 22 in mound of Earth with charred stake, pits &c as per instructions.

MONUMENT AND ACCESSORIES FOUND: State Highway No. 37 centerline, centerline of Fulton Road extending East and field line extending West.

MONUMENT MARKING DETAIL:

W.C.
30.00 FT.
----->
T3N R32E
S16 | S15
S21 | S22
2004
PLS 1106

MONUMENT SET: Accepted intersection of centerlines of State Highway No. 37 and Fulton Road, with a farmed field line extending West as best remaining evidence of the original corner location. To avoid State Highway, set a witness corner monument, a 2 1/2" brass cap on 1 1/4" x 30" galvanized iron pipe with cap buried 8" below ground level. Cap is marked as shown in "Monument Marking Detail". The witness corner monument is located North 89°42'29" West, 30.00 feet from the true corner point in State Highway No. 37.

New Accessories:

- A 3/4" brass washer stamped "PLS 1106", nailed 1.0 foot above ground level on PPL pole #150061 bears N 71° E, 61.8 feet.
 - The base (at ground level) of a post holding a group of mailboxes bears S 45° E, 72.0 feet.
 - A 3/4" brass washer stamped "PLS 1106", nailed 1.0 foot above ground level in PPL pole #220960 bears S 24° E, 136.6 feet.
 - A 3" brass disk in concrete post, 2" above ground level, (PP&L BM year 1926, El=1552.0 feet), bears N 03°13'35" E, 27.04 feet.
- Attached bearing object signs to power pole accessories.

LOCATION AND COMMENTS:

Witness corner monument falls on West side of State Highway No. 37 at Fulton Road.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Marc Hammersla
N3N32N13

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-04