

# OREGON CORNER RESTORATION FORM

**COUNTY:** Umatilla

**DATE:** 08-27-2012

## CORNER DESIGNATION:

R-7, The South Quarter Corner of Section 20, Township 3 North, Range 32 East, Willamette Meridian, Umatilla County, Oregon.

## PREVIOUS RENEWALS / SURVEYS, ETC.:


The corner was originally established by U.S. Deputy Surveyor, Daniel Chaplin, under contract No. 107 in 1864, who set a stone (15" x 12" x 10") for Quarter corner.

An undated, hand prepared sketch found in the records of the Umatilla County Surveyors Office shows the hand written note "marked stone 1/4, bottle under". It appears that this sketch is from the old Hayes and Harris files.

## MONUMENT AND ACCESSORIES FOUND:

Accepted intersection of field berm lines North and East as the best remaining evidence of the South line of Section 20. See the 2012 J-U-B Engineers, Inc. Partition Plat for Tim Weidert for complete survey and corner details.

## MONUMENT MARKING DETAIL:



## MONUMENT SET:

Set 2-1/4" x 18" Aluminum pipe with a 3-1/4" Aluminum Cap with Deep-1 magnet in concrete, buried 18" below ground surface, 15' North of drainage ditch. The Aluminum Cap is marked as shown above in the Monument Marking Detail.

## NEW ACCESSORIES:

Set mag nail with red plastic washer stamped "JUB Control" in 6-0' tall lone wooden fence post, 1.0' above ground in North side of said fence post which bears S81°E, 14.43' from Aluminum Cap.

Set a 1/2" x 24" iron rebar with red plastic cap stamped "JUB Control", 18" below ground surface which bears N07°W, 15.07' from Aluminum Cap.

## LOCATION AND COMMENTS:

The corner is located in a wheat field.

**RECEIVED BY**

Umatilla County Surveyor  
Date: 9/10/12  
Rec'd By: J. Res  
No.: 12-122-R

**REFERENCE OBJECT MEASUREMENT PROCEDURE:**

Reference bearings were obtained with a Silva Ranger Compass with a declination of 15° East.  
Reference distances were measured using a 100-foot steel tape.

**FIRM / AGENCY:**

J-U-B Engineers, Inc.  
2810 W. Clearwater Avenue, Suite 201  
Kennewick, WA 99336  
509-783-21445


**WITNESSES:**

Steven Day, Party Chief  
Felipe Hernandez, Instrument Man

**SURVEYOR'S SEAL**

08-27-2012

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR



OREGON  
JAN 16, 1996  
JOHN JOSEPH SHEA  
2751LS

RENEWAL DATE: 6-30-14

**RECEIVED BY**

Umatilla County Surveyor  
Date: 9/10/12  
Rec'd By: [Signature]  
No.: 12-122-R