

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 04/12/13

CORNER DESIGNATION: 3N32, R09, The Southeast Corner of Section 20.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under GLO Contract dated September 1864, notes state: Set post for corner to secs. 20, 21, 28 & 29 in mound of earth with charred stake and pits as per instructions. Survey 414, Book 2, Page 288, by Willard Bradley states: replaced old stake by stone marked "+". Survey 12-126-B, by John Shea, accepted a lone railroad tie fence post as the corner.

MONUMENT AND ACCESSORIES FOUND: Found set stone 12" x 10" x 5", 8" below ground surface 1.5 feet West of railroad tie fence post. One inch long mark on top, very porous stone, no other marks.

MONUMENT MARKING DETAIL:

T3N R32E  
S20|S21  
S29|S28  
2013  
PLS 54657

MONUMENT SET: At position of found stone, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top flush with the ground, set stone on North side of monument with mark visible, monument stamped as stated in "Monument Marking Detail", from which:  
A silver deep-1 magnet, buried 20" below ground, bears North 36° East, 17.2 feet.  
A purple deep-1 magnet, buried 20" below ground, bears South 58° East, 20.4 feet.  
A blue deep-1 magnet, buried 20" below ground, bears South 50 1/2° West, 18.8 feet.  
An orange deep-1 magnet, buried 20" below ground, bears North 50 1/2° West, 19.4 feet.  
All magnets have bearing object tags attached.  
Set witness post sign 1.5 feet East of monument.

LOCATION AND COMMENTS: Corner located West of railroad tie post.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:  
N= 752326.22'  
E= 8629041.05'

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS  
/3N32R09

