

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla

DATE: 08-27-2012

CORNER DESIGNATION:

T-7, The Center Quarter Corner of Section 29, Township 3 North, Range 32 East, Willamette Meridian, Umatilla County, Oregon.

PREVIOUS RENEWALS / SURVEYS, ETC.:


The survey for the establishment of Snyder Road (Road 306) in 1887 states "Set initial post 45 links East & 15 links North of Center of Section 27 and run thence on sub. 1/2 Section lines west", "160.00 chains set 2 mile post 1 link North of line". No monument is mentioned or shown in the field survey notes for the corner in question.

An undated, hand prepared sketch found in the records of the Umatilla County Surveyors Office shows the hand written note "stone, 10" x 8" x 6". It appears that this sketch is from the old Hayes and Harris files.

MONUMENT AND ACCESSORIES FOUND:

Accepted the apparent center line of Snyder Road as the best remaining evidence of the East-West center line of Section 29. See the 2012 J-U-B Engineers, Inc. Partition Plat for Tim Weidert for complete survey and corner details.

MONUMENT MARKING DETAIL:



MONUMENT SET:

Set 2-1/4" x 18" Aluminum pipe with a 3-1/4" Aluminum Cap with Deep-1 magnet in concrete, buried 15" below gravel road surface. The monument is approximately 0.5' South of the apparent center line of Snyder Road. The Aluminum Cap is marked as shown above in the Monument Marking Detail.

NEW ACCESSORIES:

Set a 1/2" x 24" iron rebar with red plastic cap stamped "JUB Control" in North shoulder of Snyder Road, 6" below road surface which bears N48°E, 14.97' from Aluminum Cap.

Found 3/4" bolt in West side of 4' tall, 8" square concrete post, set red plastic cap stamped "JUB Control" on bolt which bears S12°E, 20.41' from Aluminum Cap.

LOCATION AND COMMENTS:

The corner is located in Snyder Road.

RECEIVED BY

Umatilla County Surveyor

Date: 9/10/2012

Rec'd By: A. O'Neil

No.: 12-120-R

REFERENCE OBJECT MEASUREMENT PROCEDURE:

Reference bearings were obtained with a Silva Ranger Compass with a declination of 15° East.
Reference distances were measured using a 100-foot steel tape.

FIRM / AGENCY:

J-U-B Engineers, Inc.
2810 W. Clearwater Avenue, Suite 201
Kennewick, WA 99336
509-783-2144


WITNESSES:

Steven Day, Party Chief
Felipe Hernandez, Instrument Man

SURVEYOR'S SEAL

08-27-2012

REGISTERED
PROFESSIONAL
LAND SURVEYOR



OREGON
JAN 16, 1998
JOHN JOSEPH SHEA
2751LS

RENEWAL DATE: 6-30-14

RECEIVED BY

Umatilla County Surveyor

Date: 9/10/12

Rec'd By: A. Pres

No.: 12-120-R