

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/30/13

CORNER DESIGNATION: 3N32, V-09, The Northwest Corner of Section 33.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under GLO Contract dated September 1864, notes state: Set post for corner to secs. 28, 29, 32 & 33 in mound of earth with charred stake and pits as per instructions. Corner reestablished by John Kimbrell, 1906, Record of Private Survey Book 1, Page 580, record states: "Set iron bolt 20" long for cor to secs 28, 29, 32 and 33". Corner computed by Stephen Haddock, 10-2006, Survey 06-606-C, record states "corner point calculated using data from survey of record. No monument found or set." Corner computed by John Shea, 08/27/12, Survey No. 12-126-B, record states: "Calculated position. Corner obliterated. Held the calculated position of the Southeast corner of Section 29 as shown in survey reference No. 4 (Survey 89-123-B). Based on ties to found monuments at the Southeast corner and Southwest corner of Section 32. No monument found or set in this survey. The corner point position was located by the City of Pendleton in 1978 in Survey No. 89-123-B.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
S29|S28
S32|S33
2013
PLS 54657

MONUMENT SET: The corner point was re-established at the position determined on Survey No. 89-123-B by ties to said City survey. Corner point falls 0.20 foot North of 6" diameter green treated fence post. Set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top flush with ground marked as shown in "Monument Marking Detail" from which:
A silver deep-1 magnet, buried 20" in the ground, bears North 43° East, 28.2 feet.
A purple deep-1 magnet, buried 20" in the ground, bears South 43° East, 36.1 feet.
A blue deep-1 magnet, buried 20" in the ground, bears South 42 1/2° West, 42.2 feet.
An orange deep-1 magnet, buried 20" in the ground, bears North 60° West, 44.8 feet.
Attached witness post sign to fence post near monument, buried bearing object signs with magnets.

LOCATION AND COMMENTS: Corner is 0.20 feet North of 6" diameter green treated fence post.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 747011.24'
E= 8629193.99'


FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS

/3N33V09



RENEWS: 6-30-14