

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 08/14/13

CORNER DESIGNATION: 3N32, X17, The West One-Quarter Corner of Section 35.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of Earth with charred stake pits & c as per instructions. Corner position computed by single proportion measurement by Stephen Haddock, Survey 06-606-C, record states: "Corner point calculated following the 1973 BLM Manual of Instructions. Nothing found or set."

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E  
1/4  
S34 | S35  
2013  
PLS 54657

MONUMENT SET: Reestablished the corner position by single proportion measure between the Northwest and Southwest corners of Section 35 as did Haddock on his Survey No. 06-606-C. At the reestablished corner position, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top flush with ground, marked as shown in "Monument Marking Detail", from which:  
A 3/4" brass washer stamped "PLS 1106" in PP&L pole #350561 bears North 13° East, 185.1 feet.  
A 3/4" brass washer stamped "PLS 1106" in a PP&L pole #350460 bears South 30° East, 79.6 feet.  
A 5/8" x 24" rebar with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54657" in road bank bears South 09° West, 46.9 feet.  
A 5/8" x 24" rebar with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54657" in road bank bears North 08° West, 36.1 feet.

LOCATION AND COMMENTS: Corner located four feet West of West edge of gravel Campbell Road.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:  
N= 744562.27'  
E= 8639814.91'

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy  
\\3N32X17

