

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. A-25

Note: Monument marked as shown below


History of original corner establishment:

This corner was originally established by D. Thompson, U.S. Deputy Surveyor, under Contract No. 106, dated August 16, 1884. The original notes state that at the corner a wood post, with charred stake, earth mound and pits was set for the corner.

Record of Private Surveys, Book 1, located in the Umatilla County Surveyor's Office at page 318, shows a statement by John Kimbrell, that he made surveys and set corners for certain corners in Section 1. Kimbrell's map on page 310 indicates that he recovered the corner prior to 1895.

Map No. G-1121-B in the County Surveyor's Office, shows that Wayne Harris found a brass cap monument in 1978.

Contacts of area surveyor's did not disclose any useful information which shows how or why the monument was set. The monument is believed to have been set in 1972 or 1973. The monument is stamped by Dave Krunbein, PLS 933.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

Found and accepted the position of the 2 3/4" brass cap monument. The brass cap is on a 1 1/2" galv. iron pipe and was found protruding 12" from a mound of earth and stone. The monument is located 5' north and 10' west of a fence corner with fences running north, south and west.

Description of monument and accessories established to perpetuate the

original location of this corner:

Maintained the corner by mounding with additional earth and stone. Referenced the corner as follows. From the existing monument:

The base of a red steel fence post in the east-west fence (the second steel fence post west of the fence corner), bears S73°W 14.9'.

An aluminum nail in the south side of the wood fence corner post bears S58°E 10.67'. The nail is about 1' above ground. Attached witness corner and bearing object sign to the fence corner post.

A 1 1/2" plastic cap, marked "W.R. Wells PLS 1106", set on a 5/8" by 30" iron rod bears N45°E 14.88'. Set steel fence post near the reference monument and attached witness corner and bearing object signs.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)