

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. A-5


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by D. Thompson, U.S. Deputy Surveyor, under Contract No. 106 dated August 16, 1864. The original notes state that at the corner a wood post was set with charred stake, earth mound and pits.

In 1904, John Kimbrell, in performing County Survey No. 212, recovered the original corner and re-monumented it as follows: "The corner to Secs. 5, 6, 31, and 32, at which point I set a stone 18 by 9 by 6 for the corner in road E by N".

This corner was re-monumented by City crews in 1974 with the present brass cap monument.



Corner No.
Compass Declination: 18.0

Description of corner evidence found:

Found 2" brass cap set in concrete, flush with top of the asphalt on an abandoned road. The cap is marked as shown.

Description of monument and accessories I established to perpetuate the original location of this corner:

The existing brass cap is solidly and permanently set so no new monument was installed. I added section, township and range markings on cap, and the cap is now marked as shown on the corner diagram. From the existing monument, reference monuments bear as follows:

A 1 1/2" yellow plastic cap marked "W.R. Wells PLS 1106", set on a 5/8" by 30" iron rod bears N69°E 42.90'.

A 1 1/2" aluminum cap, marked as shown, set on a 5/8" by 30" iron rod bears S69°W 23.88'.

A cross cut in the west side of the ring of an existing manhole is located 29.06' from the existing monument.

Set steel fence posts with witness corner and bearing object signs attached near each reference monument.

The aluminum cap on the reference monument is marked:

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....

..... by
(COUNTY OFFICIAL) (DEPUTY)