

**OREGON CORNER RESTORATION FORM**

Section: 10, 11 Township: 3N Range: 33E  
County: Umatilla Date: 5/25/2011

Corner Designation: 3N33G17

Quarter corner common to Sections 10, 11, T3NR33E.

	Condition Report Only
X	Not Found
X	Remonumented
	Unrecorded
X	Surveyed In
X	Referenced Out


**Previous Renewals / Surveys, etc.**

Originally surveyed by Chaplin in 1864. He set a post in a mound of earth.

**Monuments and Accessories Found: (Condition and Source):**

None.

Diagram



Sketch

ORANGE  
MAGNET

SILVER  
MAGNET

FIELD LINE



BLUE  
MAGNET

PINK  
MAGNET

NAD 83/91  
OREGON STATE PLANE NORTH  
INTERNATIONAL FEET

N766310.33  
E8671021.69

**Monument(s) Set (Procedures and Description):**

A 1 1/8" x 30" galvanized iron pipe with a 2 1/2" brass cap, stamped as shown above, 1.4' below the surface. The corner location was reestablished by a combination of single proportionate method and holding a long established field line.

**References Set:**

- "Deep One" magnets by Berntsen.
- An orange magnet lies N 43° 15' W, 22.70', 1.3' deep.
- A silver magnet lies N 26° E, 22.17', 1.2' deep.
- A pink magnet lies S 49° E, 17.73', 1.4' deep.
- A blue magnet lies S 47° W, 20.00', 1.3' deep.

**Location and Comments:**

The corner is located 1/2 mile South and 1/2 mile West of the intersection of Deining Rd. and the Helix Hwy.

**Compass Declination**

17° E

**Surveyors Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. English*  
OREGON  
JANUARY 11, 2005  
ROBERT DOUGLAS ENGLISH  
43406LS

**RECEIVED BY:**

**Firm / Agency**

Date: 2/10/2012  
Rec'd By: S. Allen  
No. 12-094-C

Survey One, LLC.  
P.O. Box 382  
Pendleton, OR 97801  
(541) 276-2055

RENEWAL DATE: 12/31/13