

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 08/13/07

CORNER DESIGNATION: 3N33, N9. The Northwest Corner of Section 21.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was originally established by Daniel Chaplin under Contract No. 107, dated September 21, 1864. Original Notes state: "Set post for to Secs. 16,17, 20 & 21 in mound of earth with charred stake, pits and etc., as per instructions".

A fence corner was accepted for the corner point by Wayne O. Harris, LS 346, under Umatilla County Survey No. 03-154-A. This survey is dated June 28, 1956.

MONUMENT AND ACCESSORIES FOUND: Found a old fence corner with fences extending East and North, and accepted as best remaining evidence of the original corner position.

MONUMENT MARKING DETAIL:

T3N R33E
S17|S16

S20|S21
2007
PLS 1106

MONUMENT SET:

At a point 8 inches West of the fence corner, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe, 28" in the ground to monument the corner point.

New accessories:

A 5/8" by 24" rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears N 04°E, 26.9', with bearing object sign attached.

A 5/8" by 24" rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears N 04°E, 53.6', with bearing object sign attached.

A 5/8" by 24" rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears S 86°E, 16.9', with bearing object sign attached.

A 5/8" by 24" rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears S 86°E, 40.9', with bearing object sign attached.

Nailed "Witness" sign to the fence corner post by the corner monument.

LOCATION AND COMMENTS: Corner is located at fence corner at edge of fields, 1/2 mile East of Myrick Road.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, LSIT, Micah Engum

3N33N9

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-08