

**OREGON CORNER RESTORATION FORM**

Section: 23, 24, 25, 26 Township: 3N Range: 33E  
 County: Umatilla Date: 1/18/2012

Corner Designation: 3N33R21

Section corner common to Sections 23, 24, 25, 26, T3NR33E.

|              |                       |
|--------------|-----------------------|
| _____        | Condition Report Only |
| <u>  X  </u> | Not Found             |
| _____        | Remonumented          |
| _____        | Unrecorded            |
| <u>  X  </u> | Surveyed In           |
| <u>  X  </u> | Referenced Out        |


**Previous Renewals / Surveys, etc.**

Originally surveyed by Chaplin in 1864. He set a post in a mound of earth, with charred stake and pits.  
 In 1871 Moody set a post in a mound of earth.  
 In 1887 Currin and Noland set a post in a mound of earth and dug pits in each section.

**Monuments and Accessories Found: (Condition and Source):**

None.

Diagram



Sketch

ORANGE  
MAGNET

SILVER  
MAGNET

BC

NAD 83/91  
 OREGON STATE PLANE NORTH  
 INTERNATIONAL FEET

TUBBS RANCH RD.

N753225.97  
 E8676603.75

IR  
 SFP

PINK  
MAGNET

**Monument(s) Set (Procedures and Description):**

A 1 1/8" x 30" galvanized iron pipe with 2 1/2" brass cap, stamped as shown above, 1.1' below the surface of Tubbs Ranch Rd. The corner location was reestablished at the intersection of the road centerline and the field line to the South. This provides a good fit to the GLO distance from the East.

**References Set:**

"Deep One" magnets by Berntsen.  
 An orange magnet lies N 32° 20' W, 20.92', 1.5' deep.  
 A silver magnet lies N 45° 50' E, 26.53', 1.5' deep.  
 A pink magnet lies S 44° 30' E, 30.49', 1.5' deep.  
 A 5/8" x 30" iron rebar w/RPC #43406 lies S 12° 30' W, 18.11', on the North side of a steel fence post.

**Location and Comments:**

The corner is located 0.4 miles East of the intersection of Hwy. 11 and Tubbs Ranch Rd.

**Compass Declination**

17° E

**Surveyors Seal**

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Robert D. English*

OREGON  
 JANUARY 11, 2005  
 ROBERT DOUGLAS ENGLISH  
 43406LS

RENEWAL DATE: 12/31/13

**RECEIVED BY:**

Date: 7/10/2012  
 Rec'd By: S. Oles  
 No. 12-094-C

**Firm / Agency**

Survey One, LLC.  
 P.O. Box 382  
 Pendleton, OR 97801  
 (541) 276-2055