

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 08/13/07

CORNER DESIGNATION: 3N33, R9. The Northwest Corner of Section 28.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner was originally established by Daniel Chaplin under Contract No. 107, dated September 21, 1864. Original Notes state: "Set stone 20 x 10 x 10 for corner to Secs. 20, 21, 28 & 29".

In 1940, BPA surveyors accepted a fence corner with fences South and West as the corner, in survey for BPA Walla Walla - Pendleton transmission line.

**MONUMENT AND ACCESSORIES FOUND:** Corner area falls in a rocky draw with remnants of old East-West fence and a old barrel filled with stones. The corner area has been used as a rock dump for stones removed from adjoining fields. We tied into the existing BPA power transmission line at BPA Stations 1150+71.2 and 1122+25, compared our measurements to the BPA record, and finding close agreement, reestablished the corner point based on the BPA tie shown on the 1940 transmission line maps.

**MONUMENT MARKING DETAIL:**

T3N R33E  
S20|S21  
-----  
S29|S28  
2007  
PLS 1106

**MONUMENT SET:**

At reestablished corner point, drove a 5/8" by 30" rebar 27" in the ground, and capped with a 2" Bernsten plastic sleeved aluminum cap marked as shown in Monument Marking Detail. Placed a small mound of stone around new monument.

**New accessories:**

A 5/8" by 24" rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears S 87°E, 22.5', with bearing object sign attached.

A 5/8" by 24" rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears N 24°W, 24.0', with bearing object sign attached.

A 5/8" by 24" rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears N 30°W, 64.7', with bearing object sign attached.

A 5/8" by 24" rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears N 89 1/2°W, 76.5', with bearing object sign attached.

Set a steel fence post with "Witness" sign attached, 2 feet North of corner monument.

**LOCATION AND COMMENTS:** Corner is located in a small rocky draw which has been used as a rock dump for rocks from adjoining fields.

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT, Micah Engum

\3N33R9

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-08*

*27-728-01*