

CLASSIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.

Corner Code No. Z-9

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Odell and Lewis, U.S. Deputy Surveyors, under Contract No. 110, dated February 7, 1863, the original notes state that at the corner a wood post was set from which:

- A 18" fir bears North 20 lks.
- A 18" fir bears S80°W 64 lks.
- A 6" pine bears S40°W 18 lks.

DIAGRAM

T4N R36E
S32 S33
S5 S4
T3N
1988
PLS 1106

Corner No. Compass Declination: 19.0°

Description of corner evidence found:

Found the 4' long piece of the Section 5 bearing tree, with scribes "T3N" visible, wired to an old fence coming in from the Northwest.

Description of monument and accessories established to perpetuate the original location of this corner:

After a thorough search, no trace of the stump of the found bearing tree was found. The corner was reestablished at a point N40°E 11.9' from the bearing tree remains wired to the fence. Set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe 26" in the ground and surrounded with a mound of earth and stone from which:

- A 8" douglas fir bears N61°W 5.3' scribed T4N R36E S32 BT.
 - A 7" ponderosa pine bears S25°E 69.9' scribed T3N R36E S4 BT.
- No other trees are convenient for reference.

Attached bearing object sign to each bearing tree and set a steel fence post west of the corner with witness corner sign attached.

The corner is located 5' west of a fence running north from the corner area at a bearing of N14°W.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

7-27-88

Office of Survey County of Umatilla
 State of OR I hereby certify that the within instrument was filed in this office
 for record on the 28th day of July 1988
David H. Kumbert by Kathleen K. Ambrose
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor GPO-786-276

Date 7-88

Rec'd By [Signature]

No. 88-42-C