

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPC.
Umatilla County Surveyor's Office

SECTION 19	TOWNSHIP 3N	RANGE 36E
COUNTY: Umatilla		DATE 6/20/08
CORNER DESIGNATION: P-4 Center East 1/16 corner, section 19		(Please check one)
		<input checked="" type="checkbox"/> Condition Report Only
		<input type="checkbox"/> Not Found
		<input type="checkbox"/> Renewed
		<input type="checkbox"/> Unrecorded
		<input type="checkbox"/> Surveyed In
		<input type="checkbox"/> Referenced Out
Previous Renewals / Surveys, etc.		
Originally set by U.S. Deputy Surveyor James Currin, under his contract No. 537, Dated: March 5, 1889. The surveyor's field notes state "Set Post 3 feet long, 3 ins. Square with a Charred Stake 12 ins. In the ground, marked 1/16 S. on the N. face, dug pits 18x18x12 ins. E. and W. of Post 5 1/2 feet dist. and raised mound of earth 1 1/2 feet high, 3 1/2 feet base". In 1919 U.S. Indian Services Surveyor, C.E. Redfield found the original corner and set an Iron Post.		
Monument(s) & Accessories Found: (Condition & Source)		
Found a 2" Galvanized Iron Pipe with a 2 1/2" Brass Cap, in a large rock mound that appears to be an old fence corner jack.		
Monument Detail:	Sketch:	
Monument Set (Procedures and Description):		
New Accessories: NONE		
Location & Comments:		Compass Declination:
The corner is located on the South edge of a flat open field on the breaks of the Umatilla River.		
Firm / Agency USKH Address: 5 N. Colville St., Walla Walla, Wa 99632		SURVEYOR'S SEAL
Party Chief Greg E. Flowers		REGISTERED PROFESSIONAL LAND SURVEYOR
Notes		
Witness Damon Locke		OREGON JUNE 30, 1997 GREG E. FLOWERS 02820LS RENEWS 12/13/12 6/30/08

D8-112-C