

CERTIFIED RECORD OF LAND CORNER MONUMENTATION  
-----

History of original corner establishment:

Index: Q-9

South 1/16 corner Sec. 20 & 21, T.3N., R.36E., W. M.

The original survey of this line was made by Currin and Noland in 1887. They set the section corner to the south and the quarter corner 40.00 chains to the north.

1	DIAGRAM	1
1		1
1	T3N R36E	1
1	1	1
1	S ---	1
1	16	1
1	S20 S21	1
1	1996	1
1	PLS 852	1
1		1

C. E. Redfield retraced this line in 1919 and set a steel pipe with brass cap in place of Currin and Noland's original monuments. In addition, Redfield set a steel pipe with brass cap for the sixteenth corners. Redfield's record does not state what measurement the sixteenth corner was set at.

Therefore it is assumed that the original monument was set at the midpoint between the Currin and Noland monument locations.

Description of corner evidence found:

No evidence of the original corner was found. The proportioned point fell on about 1 foot east of a north-south fence line.


Description of monument and accessories I established to perpetuate the original location of this corner:

At the midpoint of the line between the found section corner to the south and the quarter corner to the north, I set a 2 1/2 inch by 30" aluminum pipe with 2 1/2 inch aluminum cap, stamped as shown in the diagram above 12 inches into the ground surrounded by a stone mound.


From which:

I set two 5/8 inch by 24 inch steel rods with aluminum cap stamped ORLS 852 and WAL5 13922 and B.O. These bearing objects bear N48 03'E, 21.7' and S45 21'E, 29.0'.

This work was done February 14, 1996.



*David L. Haddock*



Office of \_\_\_\_\_ County of \_\_\_\_\_  
State of \_\_\_\_\_, I hereby certify that the within instrument was filed  
in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_.

( COUNTY OFFICIAL )

by \_\_\_\_\_

( DEPUTY )

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 2-96  
Rec'd By KK  
No. 96-24-B