

USDA-FOREST SERVICE

Index

File No. V-23

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. _____

T 3N R. 36E

R.D. Walla Walla

County Umatilla

Merid. Willamette


N.F. Umatilla

State Oregon

CORNER DIAGRAM Sec. 36

DESCRIBE CORNER MONUMENT FOUND

Searched for but not found.



DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

PHOTO IDENTIFICATION DATA

Photo No. 1280-56

Filed At. Umatilla N.F.

Object Ident. two I.P.'s

Ident. By L. [Signature]
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is located about 450 ft. North of where Boise Cascade Co. road crosses ridge 50 ft. West of ridge top.

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____
Agency

Signature Larry D. [Signature] Title Land Surveyor Division _____ Headquarters _____ Date 6/83 7100-52-(3.68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2½"x30" Aluminum pipe with a 3" Aluminum cap 6" in ground-built stone & earth mound 6ft. base 20" high.

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

12" D-Fir N15½E-111.7 ft. scribed ¼S25BT and with a 1" Brass disk stamped PLS 896.
14" D-Fir S13W-157.0 ft. scribed ¼S36BT and with a 1" Brass disk stamped PLS 896.

Work Done By Larry D. Bishop Title Surveyor Date 6/83 State Registration No. 896
or Agency

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Set guard post East with signs 54-2 and 54-4.
Nailed 54-4 and BT signs to BT's and painted band and blazes red.