

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

x-25


History of original corner establishment:

Corner originally monumented by William H. Odell under contract No. 114 in 1866, and again by William E. Campbell under contract No. 918 in 1900,

Stone, 24"x12"x4", 18" in the ground, marked ¼ on West face.

10" diam., Fir, N. 10°W., 50 links, marked ¼SBT.

Note: No restoration notes appear in county records.



Description of corner evidence found:

Downed and rotted B.T. with reverse scribing, N.10°W., 23.0', (33.0') from cornerstone. Cornstone set firmly in place, no marks visible on stone.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Clayton J. Martin

OREGON
JULY 18, 1900
CLAYTON-JESSE MARTIN
1910

C.J. MARTIN SURVEYING
2751 JUNIPER ST.
SWEET HOME, OR 97386

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2½" diam. brass cap in a 2"x30" iron pipe at corner and buried cornerstone alongside pipe.

Cap Stamped

T3N
R36E | R37E
¼S36
RPLS 1910
1982

12" D.B.H. White Fir, S.29°W., 2.0', scribed ¼S36BT

6" D.B.H. White Fir, N.87°W., 12.5', scribed ¼S36BT

Both B.T.'s, have brass washers marked RPLS 1910 between B&T, red painted bands, B.T. tags and attention signs. Steel fence post 4.0'+ North and South of Corner with Attention, monument and boundary signs attached.

Office of Surveyor County of Wasilla
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 15 day of December, 1982
Daniel H. Kambler by Betty L. Shultz
 (COUNTY OFFICIAL) (DEPUTY)

02-112-R