

Index

File No. Z-21

**CORNER RECORD (SEARCH)**

(Ref. FSM 7151.4)

Tract or

Survey No. \_\_\_\_\_

Cor.

No. \_\_\_\_\_

T 3N R. 36E

R.D. Walla Walla

County Umatilla

Merid. Willamette


N.F. Umatilla

State Oregon

CORNER DIAGRAM Sec. 36

DESCRIBE CORNER MONUMENT FOUND

Searched for but not found.



DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

PHOTO IDENTIFICATION DATA

Photo No. 1280-54

Filed At. Umatilla N.F.

Object Ident. Direct

Ident. By L. Bishop  
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

After crossing the East line of Section 36 take the first left fork in Boise Cascade logging road to old Jeep road Northwest. Follow old Jeep road to top of ridge. Go S10W 1500 feet to corner.

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_  
Agency

Signature

*Larry D. Bishop*

Title  
Land Surveyor

Division

Headquarters

Date

6/83

7100-52-(3-68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Set 2½"x30" Aluminum pipe with a 2½" Aluminum cap 20" in ground. Built mound of stone 3 ft. base 10" high.

**ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

Drove R/R spike into exposed bedrock in rivulet N66½W-237.3 ft..  
Chisled XBO on top of point of rock outcrop N76E-48.0 ft..

Work Done By Larry D. Bishop Title Surveyor Date 6/83 State Registration No. 896  
or Agency \_\_\_\_\_  
Certified Cor. Record Prepared ? Yes No  Filed At: \_\_\_\_\_ Date \_\_\_\_\_

**REMARKS**

Set guard post North & East with signs 54-4 and 54-2.