

USDA-FOREST SERVICE


Index _____
 File No. Z-23
 T 3N R. 36E
 Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____
 R.D. Walla Walla County Umatilla
 N.F. Umatilla State Oregon

CORNER DIAGRAM Sec. 36



DESCRIBE CORNER MONUMENT FOUND

Searched for but not found.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

PHOTO IDENTIFICATION DATA

Photo No. 1280-56
 Filed At. Umatilla N.F.
 Object Ident. Direct
 Ident. By L. Wickup
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the end of the rock on Rd. #3128 follow dirt spur West 0.6 mi. to meadow to the North. Cross meadow to posted line and follow West to corner 5 feet into brush.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
Agency

Larry D. Wickup
 Signature

Title
 Land Surveyor

Division

Headquarters

Date

6/83

7100-52-(3,68)

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2½"x30" Aluminum pipe with a 2½" Aluminum cap 25" in ground.

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

18" Wh.Fir N67W-73.3 ft. scribed ¼S36BT and with a 1" Brass disk stamped PLS 896.
5/8" x 30" Iron rod N42E-14.1 feet.

Work Done By Larry D. Bishop Title Surveyor Date 6/83 State Registration No. 896
or Agency _____

Certified Cor. Record Prepared ? Yes No Filed At: _____ Date _____

REMARKS

Set guard post East with signs 54-2 and 54-4.
Nailed 54-4 and BT sign to BT and painted band and blaze red.