


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C-22

C-W 1/6 Cor. Sec. 1, T3N R37E

History of original corner establishment:

No Record



C-22

Description of corner evidence found:

NONE.

Description of monument and accessories established to perpetuate the original location of this corner:

SET A 2" x 30" ALUMINUM PIPE WITH 2 1/2" ALUMINUM CAP, MARKED AS SHOWN ABOVE, 24" IN GROUND, FROM WHICH:

A PINE, 9" DIAM., SCRIBED "CW 1/6 S1 BT" BEARS N 83 1/2° E, 25.1 FT.

A PINE, 9" DIAM., SCRIBED "CW 1/6 S1 BT" BEARS S 13 3/4° E, 51.9 FT.

SET A STEEL POST 3' SOUTH OF COR. WITH SIGN 54-4.

PAINTED A RED BAND AROUND BOTH BT'S, AND ATTACHED SIGN 54-3 ABOVE BLAZE AND SIGN 54-4 TO BACK OF TREES.

REGISTERED PROFESSIONAL LAND SURVEYOR

Victor M. McKind

OREGON JULY 17, 1970 VICTOR M. MCLIND 934

RECEIVED BY

Umatilla County Surveyor

Date 7-31-86

Rec'd By [Signature]

No. 86-95-R

Office of SURVEYOR County of UMATILLA

State of OREGON, I hereby certify that the within instrument was filed in this office for record on the day of 1986.

(COUNTY OFFICIAL) by (DEPUTY)