

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 3N, R 37E., W.M.

Corner Code No. D-25


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by J.D. Hanley as shown on Record Survey Map No. L-56. Record Certificate No. D-1221, recorded with Map L-56 states:

Set a 2 1/2" brass cap on a 2" iron pipe 31" long at base of south side of a 14" fir with a 6" steel fence post 3' south with sign 54-4 attached. Placed sign 54-2 on north and west side of 14" fir.

From which:
A larch 1 1/2" diam. bears S 50° W., 51.75 ft. dist. marked S 1/16 S1 BT with sign 54-3 attached 6" below a band of red paint and with a brass washer marked RPE 2808 nailed flush with BT blaze.



D-25

Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found 2 1/2" brass cap on 2 1/2" galvanized iron pipe projecting 3" out of the ground on the Southeast side of a 18" white fir from which:

A 16" western larch bears S 50° W, 51.75' with a partly healed double blaze.

Description of monument and accessories established to perpetuate the original location of this corner:

Maintained corner by remounding monument.

Set steel fence post South of corner and attached signs 54-2 and 54-9.

Marked 1 new bearing tree:

A 15" western larch bears N 81 1/2° W, 77.6' scribed S 1/16 S1 BT.

New bearing tree has a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-3 and 54-9 and painted face of blaze and a 6" red band around all bearing trees.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....
 State of..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19....
 by
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 1-92
 Rec'd By KK
 No. 92-02-R