


Index _____
 File No. X-21 **CORNER RECORD (SEARCH)** (Ref. FSM 7151.4) Tract or _____ Cor. _____
 T 3N R. 37E R.D. WALLA WALLA County UMATILLA Survey No. _____ No. _____
 Merid. WILLAMETTE N.F. UMATILLA State OREGON

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found no evidence of the original corner monument.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

Found a 28 inch diameter Ponderosa Pine S10°E, 173 lks, alive and vigorous with blaze evident.

Found a 25 inch diameter Douglas Fir N45°W, 78 lks, alive and vigorous with blaze evident.

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
 Signature _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on steep West face approximately 300 feet below top of ridge. No nearby roads.

PLANE COORDINATE POSITION DATA


State _____ Zone _____
 X _____
 Y _____
 Estab. By _____

Signature [Handwritten Signature] Title SURVEYOR Division _____ Headquarters _____ Date 9-6-91 FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2½"x30" aluminum pipe with aluminum cap marked as shown:
Pipe is set 24 inches in the ground.



Raised mound of stone around monument, 4 ft. base to top of cap

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New BOs:

A 5/8"x30" iron pin with plastic cap marked BGA SURVEY MARKER bears East, 3.35 feet
A 5/8"x30" iron pin with plastic cap marked BGA SURVEY MARKER bears South, 3.65 feet

Attached Bearing Tree and Land Survey Monument signs to the BTs
Set a steel fencepost approximately 5 feet East with
Land Survey Monument and Wilderness Boundary signs attached.

Work Done By. D.I. Griffith Title Surveyor Date 8-01-91 State Registration No. OPLS 644
or Agency

Certified Cor. Record Prepared ? Yes No Filed At: Umatilla Co. Surveyor Off. Date 10-91

REMARKS

Witnesses: Jeff Petersen and Jim Bennett

Index File No. X-21 T. 3N R. 37E WM. Tract or Surv. No. Cor. 12
13