


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by George S. Pershin under GLO contract number 304, dated September 19, 1878. Surveyor General record states:
 Set basalt stone 18x10x8 in mound of stone on level open glade for corner to Townships 2 and 3 North, Ranges 37 and 38 East Willamette Meridian from which;
 Fir 28 in diam brs S24°W, 210 lks dist
 Fir 28 in diam brs N46°W, 340 lks dist
 No other trees near.



Corner found by William E. Campbell under GLO contract number 718, dated May 1, 1900. Surveyor General record states:
 The SE Cor of T3N R37E is a basalt stone 18x10x8 ins... marked and witnessed as described by the Surveyor General. I destroy the marks on the SW witness tree and marks on the cor stone as pertain to T2N R38E

No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found a basalt stone 18x12x10 inches marked with 6 grooves on three faces, in a mound of stone.

Found a 36 inch diameter Douglas Fir snag, S24°W, 210 lks with blaze evident. (Did not open).

Found the badly rotted remains of Douglas Fir N40°W, 331 lks dead and down with rotted chop marks only.

Description of monument and accessories I established to perpetuate the original location of this corner:

In place of the found original corner stone, I set a 2½" x 30" aluminum pipe with aluminum cap marked as shown, 26 inches in the ground, from which:

New Bearing Trees and Bearing Object;
 A 3'x2'x18" high rock outcrop bears N60°E, 39.55 feet marked X B0 on top of outcrop
 A 15 inch diameter Douglas Fir bears S55°W, 75.60 feet marked S1 BT
 A 13 inch diameter Douglas Fir bears S24°W, 135.32 feet marked X BT
 A 14 inch diameter Douglas Fir bears N26°W, 226.98 feet marked T3N R37E S36 BT
 Buried the original corner stone North and alongside of monument.
 Painted a 6 inch red band around all bearing trees and attached Bearing Tree and Land Survey Monument signs.

Set a steel fencepost approximately 5 feet North with Attention sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on June 23, 1991.



**REGISTERED
 PROFESSIONAL
 LAND SURVEYOR**

Duane I. Griffith
 OREGON
 JULY 10, 1964
DUANE I. GRIFFITH
 644

I used a steel tape and magnetic compass in the establishment of new accessories. I used 20° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 10-92
 Rec'd By KK
 No. 92-118-R

Z-25