

Index

File No.

T. 3 N.

R. 38 E.

Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. Walla Walla

N.F. UMATILLA

County UMATILLA

State OREGON

Tract or


Survey No. NF Umatilla

Cor.

No. AP-521

CORNER DIAGRAM

AP-521



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2,631,005.71'

Y: 762,472.25'

Datum: NAD1927

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of Oregon Highway 204 and the entrance to Woodland Park Campground descend S. 15° E., approx. 420 feet to the corner which is located in a small creek at an elevation of 5000 feet.

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

06/1996

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set in a small creek at an elevation of 5000 feet a 5/8" by 36" rebar, with a 3 1/4" aluminum cap, 33" into the creek bed, mkd. "NFU WILDERNESS AP-521 RLS 2308 1996"

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

22" White Fir, S. 74° W., 13.6 ft., mkd. "WB/512" "BT".

19" Western Larch, N. 47° W., 29.8 ft., mkd. "WB/521" "BT".

BT's are double blazed and have a 3/4" brass washer mkd. "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By **D. Schlaich**

Title **Land Surveyor**

Date **06/1996**

State Registration No.
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

3 N.

R.

38 E.

M.

W.M.

Tract or Survey No.

NF Umatilla

Cor.

AP-521