

USDA-FOREST SERVICE

Index
 File No. T. 3 N. R. 38 E.
 Merid. WILLAMETTE

CORNER RECORD (SEARCH)
 (Ref. FSM 7151.4)

Tract or
 Survey No. **NF UMATILLA**
 Cor. No. **AP-408**

R.D. WALLA-WALLA County UMATILLA
 N.F. UMATILLA State OREGON

CORNER DIAGRAM

N.F. Umatilla Wilderness

AP-408

DESCRIBE CORNER MONUMENT FOUND
 NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND
 NONE

PHOTO IDENTIFICATION DATA
 Photo No.:
 Filed At.:
 Object Ident.:
 Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER
 The corner is located on the 5000 foot contour.

PLANE COORDINATE POSITION DATA
 State: OREGON Zone: NORTH
 X: 2,688,869.470 meters
 Y: 235,031.432 meters
 Datum: NAD83(1991)

Signature	Title	Division	Headquarters	Date	FS-7100-52 (3/68)
D. Schlaich	Land Surveyor		S.O.	09/1994	

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 24" rebar, with a 3 1/4" aluminum cap, 10" in the ground and raised a mound of stone 2' in diameter by 14" high. Cap is mkd. "NFU WILDERNESS AP-408 RLS 2308 1994".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

5" Ponderosa Pine, S. 37° W., 33.2 ft., mkd. "WB/408""BT".

7" Douglas Fir, N. 31 1/2° W., 40.2 ft., mkd. "WB/408""BT".

The BT's are double blazed and have a 3/4" brass washer mkd. "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By **D. Schlaich**

Title **Land Surveyor**

Date **09/1994**

State Registration No.
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

3 N.

R.

38 E.

M.

W.M.

Tract or Survey No.

NF UMATILLA

Cor.

AP-408