

CORNER RECORD (SEARCH)
(Ref. FSM 5151.4)

T. 3 N. R. 38 E.
Merid. Willamette

R.D. WALLA-WALLA County **UMATILLA**
N.F. Umatilla State **Oregon**

CORNER DIAGRAM

**N.F. UMATILLA
WILDERNESS**



DESCRIBE CORNER MONUMENT FOUND
NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND
NONE

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By
Signature

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North
X: 2,619,217.13'
Y: 755,084.68'
Datum: NAD*1927

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER
From the junction of F.S. roads 3100 and 3100-360, travel northwesterly on road 3100-360 approx. 2.0 miles. From this point descend to the west approx. 400 feet to AP-676 which is located at the head of a small draw at an elevation of 5000 feet. From AP-676 descend westerly down the small draw to the Johnson Creek. Then proceed northwesterly down Johnson Creek approx. 1100 feet to the corner which is located at the intersection of Johnson Creek with an unnamed creek flowing in to Johnson creek from the southwest.

Signature
D. Schlaich

Title
Land Surveyor

Division

Headquarters
S.O.

Date
10/1996

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set at a point where the center thread of Johnson Creek intersects the center thread of an unnamed creek, a 6 foot steel fence post with Land Survey Monument and Wilderness Boundary signs.

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

21" White Fir, N. 52° E., 68.7 feet, scribed "WB/689" "BT".

RM, 5/8" by 24" rebar with 3 1/4" aluminum cap, set flush with ground, S. 74 1/2° E., 36.6 feet, stamped "RM WB 689 36.6 FT 2308 1996" with an arrow pointing toward the corner.

The BT is double blazed and has a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By D. Schlaich Title Land Surveyor Date 10/1996 State Registration No. or Agency _____
Certified Corner Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Index File No.

T. 3 N.

R. 38 E.

M. Willamette

Tract or Survey No. N.F. Umatilla Wild.

Cor. AP-689