

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


R-05

History of original corner establishment:

1899, John W. Kimbrell. U.S. Deputy surveyor, while surveying the township under General Land Office Contract No. 700 established the corner as follows:

Set fir post 3 ft long 3 ins Sq 24 ins in the ground for Cor of Secs 19-20-29 and 30 marked T3N S20 on NE R38E S29 on SE S30 on SW and S19 on NW faces with 2 notches on S and 5 notches on S edges, from which:

- a Willow 3 ins diam bears N68°E 17 lks dist marked T3NR38ES20B.T.
a Willow 3 ins diam bears S2°E 44 lks dist marked T3NR38ES29B.T.
a Tamarack 9 ins diam bears S1°W 175 lks dist marked T3NR38ES30B.T.
a Willow 3 ins diam bears N69°W 41 lks dist marked T3NR38ES19B.T.
NOTE: The General Land Office rejected John Kimbrell's 1899 survey.



1903, John W. Kimbrell. U.S. Deputy surveyor, while resurveying the township under General Land Office Contract No. 700 established the corner as follows:

Set basalt stone 18 X 9 X 6 ins, 12 ins in the ground for cor of secs 19, 20, 29 and 30 marked with 2 notches on S 5 notches on E sides, and raised a mound of stone 2 ft. base 1 1/2 ft high W of cor, pits impracticable.

From this cor the old sec cor, a post marked and witnessed bears N 595 lks dist. I destroy cor & marks on bearing trees.

2000, David A. Schlaich. Registered Land Surveyor No. 2308, Found a basalt stone 14 inches by 10 inches by 5 inches with 5 grooves on East face of the stone. Set in place of the stone a 2 1/2 inch diameter by 30 inch long aluminum pipe, with a 3 1/4 inch diameter aluminum cap, 22 inches in the ground (partially buried stone on North side of monument).

Marked new BT's:

- 15 inch diameter Fir bears N. 85 1/2° E., 42.9 feet, scribed "T3N R38E S20" "BT".
11 inch diameter Western Larch bears S. 20° E., 14.9 feet, scribed "T3N R38E S29" "BT".
10 inch diameter Lodgepole Pine bears S. 43 1/2° W., 10.6 feet, scribed "T3N R38E S30" "BT".
24 inch diameter Western Larch bears N. 42 1/2° W., 56.9 feet, scribed "T3N R38E S19" "BT".

The bearing trees are double blazed and have a 3/4" diameter brass washer stamped "RLS 2308" nailed to the lower blaze near the "BT" scribing.

Description of corner evidence found:

Found a 2 1/2" aluminum pipe, with a 3 1/4" aluminum cap, projecting 10" above the ground with a portion of the original basalt stone visible on the North side of the monument, marked as shown, from which:

- 16" Douglas Fir bears N. 83 1/4° E., 42.9 feet, scribing "T3NR38ES20" "BT" visible on double blaze with 3/4" brass washer "RLS 2308" nailed to the lower blaze.
11" Western Larch bears S. 23° E., 14.9 feet, scribing "T3NR38ES29" "BT" visible on double blaze with 3/4" brass washer "RLS 2308" nailed to the lower blaze.
10" Lodgepole Pine bears S. 39 1/2° W., 10.6 feet, with pitched over double blaze and 3/4" brass washer "RLS 2308" nailed to the lower blaze.
25" Western Larch bears N. 45 1/4° W., 56.9 feet, scribing "3NR38ES19" "BT" visible on double blaze with 3/4" brass washer "RLS 2308" nailed to the lower blaze.



REGISTERED PROFESSIONAL LAND SURVEYOR

David A. Schlaich

OREGON JULY 16, 1987 DAVID A. SCHLAICH 2308

Description of monument and accessories I established to perpetuate the original location of this corner:

DATUM: NAD83(CORS96) (EPOCH:2002.0000) STATE PLANE COORDINATES: Oregon North Zone in International Feet

RENEWAL DATE: 06/30/2006

Latitude Longitude Northing(y) Easting(x)
45°43'02.83424" North 118°05'50.53253" West 756798.731 8815688.885

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 20.....
(COUNTY OFFICIAL) by..... (DEPUTY)

Form R6-7100-57 (9/71)

04-212-B