

Index File No. V-5

CORNER RECORD (SEARCH)

Tract or Survey No. \_\_\_\_\_

Cor. No. \_\_\_\_\_

(Ref. FSM 7151.4)

T 3N R. 38E

R.D. WALLA WALLA County UMATILLA

Merid. WILLAMETTE


N.F. UMATILLA State OREGON

CORNER DIAGRAM

T 3N R 38E

DESCRIBE CORNER MONUMENT FOUND

NONE -



DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

ORIG. 24" FIR IS A 32" SNAG WITH A LARGE HEALED BLAZE. BEARS N 22° 30' E, 40.26 ft.  
 ORIG. 24" FIR IS A BROKEN & DECAYED STUMP. AXE MARKS ARE VISIBLE. BEARS S 7° E, 21.78 ft.  
 ORIG. 30" FIR IS A 10' HIGH BROKEN SNAG. PARTLY CHOPPED OUT SCRIBES VISIBLE. BEARS S 75° W, 17.82 ft.

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
 Filed At. \_\_\_\_\_  
 Object Ident. \_\_\_\_\_  
 Ident. By \_\_\_\_\_  
 Signature \_\_\_\_\_

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

ORIG. 20" FIR IS A BROKEN & DECAYED STUMP. PARTLY CHOPPED OUT SCRIBES ARE VISIBLE ON THE LOG LYING ALONGSIDE. STUMP BEARS N 65° 30' W, 9.9 FEET. I FOUND LINE BLAZES NORTH AND EAST OF THIS CORNER. I COULD NOT FIND THE 1903 CORNER, S 5 1/2° E, 6.04 ch.

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
 X \_\_\_\_\_  
 Y \_\_\_\_\_  
 Estab. By \_\_\_\_\_  
 Agency \_\_\_\_\_

Signature

Title

Division

Headquarters

Date

FS-7100-52 (3/68)

*Dennis J. Saylord* PLS 1636

AUG 29, 1997

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Work Done By \_\_\_\_\_ Title \_\_\_\_\_ Date \_\_\_\_\_ State Registration No. or Agency \_\_\_\_\_  
Certified Cor. Record Prepared ? Yes No Filed At: \_\_\_\_\_ Date \_\_\_\_\_

REMARKS

I PUT BT SIGNS ON THE TWO STANDING SNAGS AND A LOCATION SIGN ON A 14" FIR N35°E, 10 FEET FROM THE CORNER.

Index File No. T. R. M. Tract or Surv. No. Cor.

V-5 T3N R38E