


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Original corner established by Saxton in 1909. Harris found 1 1/2 inch iron pipe in 1976. Krumbein set 2 1/2 inch brass cap in 1980. Roberts referenced brass cap in 1995.




**Description of corner evidence found:**

Found 2 1/2 inch brass cap buried 12 inches below the road surface of the North travel lane of West Punkin Center Road, at its intersection with N.W. Geer Road; mkd: as shown.

From which I find the stated references intact and undisturbed:

- (RM 1) A 5/8 inch iron rebar with yellow plastic cap mkd: UMA CO R D LS 2627, bears N33°57'E, 38.53 feet dist.
- (RM 2) A 5/8 inch iron rebar with yellow plastic cap mkd: UMA CO R D LS 2627, bears S45°09'E, 36.27 feet dist.
- (RM 3) A 5/8 inch iron rebar with yellow plastic cap mkd: UMA CO R D LS 2627, bears S50°14'W, 48.55 feet dist.
- (RM 4) A 5/8 inch iron rebar with yellow plastic cap mkd: UMA CO R D LS 2627, bears N43°34'W, 43.63 feet dist.



**Description of monument and accessories I established to perpetuate original location of this corner:**

At surface of asphalt, I set a 2 inch MAG nail with 1 1/2 inch stainless steel washer mkd: WA LS 2872, directly over the brass cap.

NAD 83 Geodetic Position  
 Lat. 45°51'52.9" N  
 Long. 119°18'01.6" W

Established by: Trimble RTK

I hereby certify that the corner is monumented and accessories taken as described, using dual frequency carrier-phase GNSS receivers.

Witnesses: Kristina Powell and David Quittschreiber

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Rodney J. Lewis*

OREGON  
 JULY 21, 1998  
**RODNEY J. LEWIS**  
 2872

EXPIRES 12-31-18

Office of ..... County Surveyor ..... County of ..... Umatilla .....  
 State of ..... Oregon ..... , I hereby certify that the within instrument was filed in this office  
 for record on the ..... day of ..... , 2017  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)