

OREGON CORNER RESTORATION FORM

SECTION 21 TOWNSHIP 4N RANGE 28 E

N-11

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

North 1/4 Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found 2 1/2" Brass Cap in Monument Box, 0.7 ft. below surface of asphalt, set by Krumbein in 1981 in place of a monument used since 1963. Origin unknown.

MONUMENT DETAIL

SKETCH

T4N R28E
16
1/4
21
1981
933

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES From which

An Alum. tag #951 in Power pole Bears N 67° 47' 50" E 63.12 feet with Bearing Object sign attached.
A 2 1/2" Brass Cap, stamped S 40 03 E 41.24 O.R.L.S. 506, Bears N 50° 54' 40" W 41.27 feet.
A 2 1/2" Brass Cap, stamped N 48 26 E 56.46 O.R.L.S. 506, Bears S 48° 35' 30" W 56.46 feet.
An Alum. tag #951 in Power pole Bears S 58° 45' 30" E 68.67 feet with Bearing Object sign attached.

LOCATION & COMMENTS

Corner is at the intersection of Lloyd and Minnehaha Roads.

SURVEYOR'S SEAL

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS

NOTES
WITNESS S. BENEFIT

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1871
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KK

No. 92-45-C