

OREGON CORNER RESTORATION FORM

SECTION 21 TOWNSHIP 4N RANGE 28 E

N-9

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

Northwest Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed by Taft in 1860 under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found 1 1/2" Iron pipe, Bears S 0° 10' 39" E 17.00 feet from the corner, used by many surveyors since 1963. Origin unknown.

MONUMENT DETAIL

SKETCH

T4N R28E
17 16

20 21
1991
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

The 1 1/2" Iron pipe which has been used by all surveyors since at least 1963 is apparently too far South. Proportionally, it should lie about 32 feet North. I held the Eastings and set a 2 3/8" Brass Cap on 1" x 30" Iron pipe 0.6 ft. below surface of gravel driveway on the centerline of Minnehaha Road, as it was surveyed by John Kimbrell in 1907. (17 feet North of the 1 1/2" Iron pipe.) See my County Survey #1991-2.

NEW ACCESSORIES From which

An Alum. tag #951 in RR tie corral corner Bears N 8° 10' 40"E 20.87 feet with Bearing Object and Witness signs attached.
An Alum. tag #951 in Power pole Bears S 78° 05' W 86.42 feet with Bearing Object sign attached.
A 1 1/2" Iron pipe Bears S 0° 10' 39" E 17.00 feet with Bearing Object sign attached to existing steel fence post.
An Alum. tag #951 in Power pole Bears S 38° 19' 30" E 24.32 feet with Bearing Object and Witness signs attached.

LOCATION & COMMENTS

Corner is located at the intersection of Keller and Minnehaha Roads.

SURVEYOR'S SEAL

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES
WITNESS S. BENEFIT

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KK

No. 92-45-C