

OREGON CORNER RESTORATION FORM

SECTION 24 TOWNSHIP 4N RANGE 28 E

R-23

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

South 1/4 Corner

CONDITION REPORT ONLY  
 NOT FOUND  
 RENEWED  
 UNRECORDED  
 SURVEYED IN  
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Nothing found.

MONUMENT DETAIL

SKETCH

T4N R28E  
24  
1/4  
25  
1991  
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion I set a 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped as above, 0.1 foot below pavement in a 5" PVC with an alum. mon. box. See my County Survey #1991-2.

NEW ACCESSORIES From which

An Alum. tag #951 in power pole Bears N 79° 54' 00" E 198.50 feet with Bearing Object sign attached.

A 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped W.C. LS 951, Bears N 0° 03' 10" E 33.00 feet. Drove a steel fence post and attached Bearing Object and Witness signs.

An Alum. tag #951 in power pole Bears N 66° 46' 00" W 90.29 feet with Bearing Object sign attached.

A 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped W.C. LS 951, Bears S 0° 03' 10" W 33.00 feet. Drove a steel fence post and attached Bearing Object and Witness signs.

LOCATION & COMMENTS

From intersection of Ott Rd. and Feedville Road, go West on Feedville Rd. 0.5 mile to Corner.

SURVEYOR'S SEAL

COMPASS DEC.  
FIRM EDWARDS SURVEYING  
P.O. BOX 763, HERMISTON,  
OREGON, 97838

PARTY CHIEF D. EDWARDS  
NOTES

WITNESS S. BENEFIT  
RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KK

No. 92-45-C

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951