

CORNER RESTORATION FORM

Township 4N Range 28E Section 19, 20, 29, 30 County UMATILLA

State OREGON Date 5-21-2019 Number R-5

Corner Designation : 19, 20, 29, 30

Previous Renewals ORIGINAL SOURCE OF CORNER

ORIGINALLY SURVEYED IN 1860 BY HAFT UNDER CONTRACT #93. HE SET POST IN

MOUND w/TRENCH, MADE PITS & DEPOSITED A PINT OF CHARCOAL.

Accessories Found: _____

NONE.

Condition Report Only

Not Found

Renewed

Surveyed In

Referenced

MONUMENT DETAIL

Found Set

BASIS OF BEARINGS, NAD 83/91 OREGON STATE PLANE
COORDINATES NORTH ZONE:

Northing: 782221.76

Easting: 8494711.14



Monument & Accessories Set (Procedure and Description) _____

FOUND 2 1/2" BRASS CAP, AS PER COUNTY SURVEY 91-057-A.

SET 5/8" x 10" REBAR w/RED PLASTIC CAP PLS 61420, 1' DEEP, 1' SOUTH OF RR TIE GATE POST, N82°42'W, 14.96'.

SET 5/8" x 10" REBAR w/RED PLASTIC CAP PLS 61420, 1' DEEP, 1' SOUTH OF WIRE FENCE, N77°32'E, 73.47'.

SET 5/8" x 10" REBAR w/RED PLASTIC CAP PLS 61420, 1' DEEP, 1' NORTH OF RR TIE, S73°37'E, 83.33'.

SET 1 1/2" STEEL WASHER MARKED 61420, IN RR TIE w/MAG NAIL APPROX. 2' ABOVE GRADE, S84°05'W, 212.15'.

Sketch of Monument, Accessories and General Area

REGISTERED PROFESSIONAL LAND SURVEYOR

Lance Clark King

OREGON
MAY 10, 2011
LANCE CLARK KING
61420

RENEWS: 6/30/2021

Agency: CK3, LLC
 945 W. ORCHARD
 HERMISTON OREGON 97838
 OFFICE: 541-567-2345
 FAX: 541-567-2305
 WEB: CK3LLC.NET
 Field Book # 0-325

COUNTY SURVEYOR RECORDING INFO

Received _____

Filed _____

Survey No. _____

Drawing No. _____

Index No. R-5

19-080-C