

CORNER RESTORATION FORM

Township 4N Range 28E Section 20,29 County UMATILLA

State OREGON Date 5-23-2019 Number R-7

Corner Designation: 20, 29

Previous Renewals ORIGINAL SOURCE OF CORNER

ORIGINALLY SURVEYED IN 1860 BY HAFT UNDER CONTRACT #93. HE SET POST IN

MOUND w/TRENCH, MADE PITS & DEPOSITED A PINT OF CHARCOAL.

Accessories Found: _____

NONE.

Condition Report Only

Not Found

Renewed

Surveyed In


Referenced

MONUMENT DETAIL

Found Set

BASIS OF BEARINGS, NAD 83/91 OREGON STATE PLANE
COORDINATES NORTH ZONE:

NORTHING: 782238.61
EASTING: 8497364.16



Monument & Accessories Set (Procedure and Description)

FOUND 2 1/2" BRASS CAP, 2 1/2" BELOW ROAD GRADE, AS PER COUNTY SURVEY 97-169-B.

SET 5/8" x 10" REBAR w/RED PLASTIC CAP PLS 61420, 1' DEEP, 1' SOUTH OF POWER POLE, N86°43'W, 584.10 FT.

SET 1 1/2" STEEL WASHER MARKED 61420, IN POST w/MAG NAIL APPROX. 2' ABOVE GRADE, N24°27'E, 40.15 FT.

SET 5/8" x 10" REBAR w/RED PLASTIC CAP PLS 61420, 1' DEEP, 1' NORTH OF RR TIE, S85°11'W, 207.78 FT.

SET 5/8" x 10" REBAR w/RED PLASTIC CAP PLS 61420, 1' DEEP, 1' NORTH OF FENCE, & GREEN STEEL POST w/SURVEY MARKER SIGN,

S00°55'E, 16.70 FT.

Sketch of Monument, Accessories and General Area

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Lance Clark King

**OREGON
MAY 10, 2011
LANCE CLARK KING
61420**

Agency: CK3, LLC
945 W. ORCHARD
HERMISTON OREGON 97838
OFFICE: 541-567-2345
FAX: 541-567-2305
WEB: CK3LLC.NET
Field Book # 0-325

RENEWALS: 6/30/2021

**COUNTY SURVEYOR
RECORDING INFO**

Received _____

Filed _____

Survey No. _____

Drawing No. _____

Index No. R-7

19-080-2