

OREGON CORNER RESTORATION FORM

SECTION 27 TOWNSHIP 4N RANGE 28 E

T-17

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

East 1/4 Corner

CONDITION REPORT ONLY

NOT FOUND

RENEWED

UNRECORDED

x SURVEYED IN

x REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found 1/2" rebar in centerline of Hinkle Road. Origin unknown.

MONUMENT DETAIL

SKETCH

T4N R28E

1/4

27 26

1991

LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

In place of 1/2" rebar, 1 set 2 3/8" Brass Cap on 1" x 30" Iron pipe, stamped as above, 0.2 ft. below surface inside 5" P.V.C. and in an Alum. Umatilla County Monument Box set flush with asphalt in concrete. Buried 1/2" rebar along side. See my County Survey #1991-2.

NEW ACCESSORIES From which

An Alum. tag #951 in power pole Bears N 9° 07' 40" W 209.16 feet with Bearing Object sign attached.

A 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped W.C. LS 951, Bears West 33.00 feet.

An Alum. tag #951 in power pole Bears S 20° 50' 40" W 91.37 feet with Bearing Object sign attached.

A 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped W.C. LS 951, Bears East 33.00 feet.

LOCATION & COMMENTS

From intersection of Feedville Rd. & Hinkle Rd. go South 0.5 mile on Hinkle Road to the Corner.

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838

PARTY CHIEF D. EDWARDS

NOTES

WITNESS S. BENEFIT

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 18, 1971
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KK

No. 92-45-C