

OREGON CORNER RESTORATION FORM

SECTION 25 TOWNSHIP 4N RANGE 28 E

T-21

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

West 1/4 Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Nothing found.

MONUMENT DETAIL

SKETCH

MONUMENT SET (PROCEDURES AND DESCRIPTION)

Nothing set. Access denied in the middle of Hinkle Railroad Hump Yard.

NEW ACCESSORIES From which

An Alum. tag #951 on NW face of Brace pole Bears N 26° 07' 09" E 371.17 feet with Bearing Object sign attached on North side.

An Alum. tag #951 in Power pole Bears N 7° 06' 24" W 298.47 feet with Bearing Object sign attached on North side.

A 1/2" x 24" rebar with Alum. tag #951 Bears N 15° 48' 42" W 396.93 feet.

A 2 3/8" Brass Cap on 1" x 30" Iron pipe, stamped W.C. LS 951 Bears N 0° 09' 12" W 381.91 feet.

A 2 3/8" Brass Cap on 1" x 30" Iron pipe, Stamped W.C. LS 951 Bears S 0° 09' 12" E 2358.40 feet.

LOCATION & COMMENTS

In The Hinkle Hump yard. COMPASS DEC.

FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS

NOTES

WITNESS S. BENEFIT

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KK

No. 92-45-C

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951