

OREGON CORNER RESTORATION FORM

SECTION 25 TOWNSHIP 4N RANGE 28 E

T-25

COUNTY: UMATILLA DATE 8/91

CORNER DESIGNATION

East 1/4 Corner

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in October 1860 under Contract #95. W.B. Campbell set post, drove charred stake and made pits and mounds.

In 1954, Higgins set 1/2" Iron rod.

In 1980, Krumbein replaced 1/2" Iron rod with 2 1/2" Brass Cap, stamped as below.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found Krumbein's 1980 2 1/2" Brass Cap, 14" below surface of paved road.

MONUMENT DETAIL

SKETCH

T4N
R28E R29E

25 . 30

1980
RLS 933

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES From which

- An Alum. tag #951 in Power pole Bears N 05° 44' 50" W 177.72 feet with Bearing Object sign attached,
- Set Bearing Object and Witness signs on Cedar fence post with Alum. tag #951 attached, Bears N 90° 00' W 18.44 feet,
- An Alum. tag #951 in Power pole Bears S 05° 48' 20" W 184.14 feet with Bearing Object sign attached,
- An Alum. tag #951 in Power pole Bears S 24° 56' 10" E 78.98 feet with Bearing Object sign attached.

LOCATION & COMMENTS

From intersection of Feedville and Ott Rds. go South 1/2 mile to Corner.

SURVEYOR'S SEAL

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS

NOTES
WITNESS S. BENEFIT

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

G. Dennis Edwards

OREGON
JULY 16, 1871
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KK

No. 92-45-C