


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

THE EXTERIOR OF T.4 N., R.28 E., W.M. AND THE SUBDIVISION OF SAID TOWNSHIP WERE ORIGINALLY SURVEYED BY EBENEXER E. HAFT UNDER GENERAL LAND OFFICE CONTRACT NO. 93, DATED SEPTEMBER 11, 1860. THE FIELD NOTES FOR THIS SURVEY STATE: "SET POST FOR QR. SEC. CORNER IN MOUND WITH TRENCH AND PITS, AND DEPOSITED 1 PINT OF CHARCOAL AS PER INSTRUCTIONS.




FOUND AXLE: FIRST NOTED ON COUNTY SURVEY (CS) H-26-AX IN 1960. SUBSEQUENTLY NOTED ON CS M-079-C, CS 88-015-C, CS 92-045-C, PP 2006-31,

DESCRIPTION OF CORNER EVIDENCE FOUND:

TRUCK AXLE SET FLUSH WITH THE GROUND.

DESCRIPTION OF MONUMENT AND ACCESSORIES ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:

SET 1 1/4" COPPER DISK MARKED "ODOOT" W/CENTER PUNCH IN THE IMPACT PANEL OF THE BRIDGE, FROM WHICH:



- 1) A 5/8" X 30" IRON ROD WITH A 1 1/2" ALUMINUM CAP STAMPED "PLS 2733" BEARS S.53°26'25"W. 111.56 FT.
- 2) A 5/8" X 30" IRON ROD WITH YELLOW PLASTIC CAP MARKED "PLS LS48509" BEARS S.89°41'28"W. 98.28 FT.
- 3) A 5/8" X 30" IRON ROD WITH A 1 1/2" ALUMINUM CAP STAMPED "PLS 2733" BEARS N.11°04'54"E. 307.47 FT.
- 4) A 5/8" X 30" IRON ROD WITH A 1 1/2" ALUMINUM CAP STAMPED "PLS 2733" BEARS S.51°39'50"E. 77.83 FT.

THE BEARINGS SHOWN ARE BASED ON GPS SURVEY, CS 13-517-B.

WITNESSES:
KEITH WOLFORD, JOSH McCULLOUGH

I HEREBY CERTIFY THAT THE ABOVE CORNER POSITION WAS PERPETUATED AS HEREON DESCRIBED IN APRIL 8, 2016.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert E. Butler

OREGON
JULY 25, 1995
ROBERT E. BUTLER
2733

RENEWS: 12/31/2017

OREGON DEPARTMENT OF TRANSPORTATION



Section	FFO-207 UMATILLA R.(HINKLE) BR. #02318A		
Highway	HERMISTON		
County	UMATILLA	Scale	NTS
Purpose	RW MONUMENTATION	Date	APRIL 8, 2016

V-11

Rec'd. 5/26/2016
Jay Roberts

16-071-R