

OREGON CORNER RESTORATION FORM

SECTION 28 TOWNSHIP 4N RANGE 28E

V-11

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

South 1/4 Corner

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post, made pits and mound and deposited 1 pint of charcoal.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found truck axle, origin unknown, used for many years as a 1/4 Corner. It fit well with other monuments. See my County Survey 1991-2.

MONUMENT DETAIL

SKETCH

MONUMENT SET (PROCEDURES AND DESCRIPTION)

I drove steel fence post, with Witness sign attached, 2 feet Northeast.

NEW ACCESSORIES From which

A 3" Brass disc BM on SW corner of Bridge Bears N 40° 45' W 79.77 feet.

An Alum. tag #951 in Power pole Bears S 89° 55' 10" W 122.30 feet, with Bearing Object sign attached.

An Alum. tag #951 in Power pole Bears S 0° 10' 00" E 217.57 feet, with Bearing Object sign attached.

An Alum. tag #951 in Power pole Bears S 56° 28' 40" E 6.83 feet, with Bearing Object sign attached.

LOCATION & COMMENTS

At the Southeast corner of Butter Creek Hwy. Bridge over Umatilla River.

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS

NOTES

WITNESS S. BENEFIT

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1871
G. DENNIS EDWARDS
951

RECEIVED BY
Umatilla County Surveyor
Date 4-92
Rec'd By KK
No. 92-45-C