

OREGON CORNER RESTORATION FORM

SECTION 26 TOWNSHIP 4N RANGE 28E

V-21

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

SE Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. The corner fell in the Umatilla River so he set a Witness Corner 66 feet South.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Nothing found.

MONUMENT DETAIL

SKETCH

T4N R28E
26 25
35 36
1991
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

Corner falls in the Umatilla River, so did not set. Computed the location of the corner. See my 1991-2 County Monumentation Survey.

NEW ACCESSORIES From which

A 2 3/8" Brass Cap on 1" Iron pipe, stamped W.C. LS 951, Bears N 0° 09' 12" W 275.00 feet, drove steel fence post with Witness sign attached.
A 2 3/8" Brass Cap on 1" Iron pipe, stamped W.C. LS 951, Bears S 0° 09' 12" E 82.18 feet, drove steel fence post with Witness sign attached.
A 5/8" x 30" rebar with Alum. tag #951 Bears S 18° 25' 46" E 98.49 feet, drove steel fence post with Witness sign attached
A 1/2" x 30" rebar with Alum. tag #951 Bears N 24° 20' 25" E 301.80 feet.

LOCATION & COMMENTS

From the sharp curve on Umatilla Meadows Rd. where farm shop and sheds are, go North 1/2 mile and East 1000 feet to the Corner.

SURVEYOR'S SEAL

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES
WITNESS S. BENEFIT

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RECEIVED BY
Umatilla County Surveyor
Date 4-92
Rec'd By AK
No. 92-45-c